

Oct. 2024

Ki Sig Kang, Ph.D, P.E.

Professor for Special Affairs,

Department of NPP Engineering. **KINGS**

[Kisigkang4@outlook.com](mailto:Kisigkang4@outlook.com)



# KEY SUCCESS FACTORS FOR NPP CONSTRUCTION MANAGEMENT

---

# 01

## PART One

### General Information

---


# Large scale projects have a calamitous history of cost overrun

Project	Cost Overrun (%)	Project	Cost Overrun (%)
Suez Canal, Egypt	1900	Sydney Opera House, Australia	1400
Scottish Parliament Building, Scotland	1600	Montreal Summer Olympic, Canada	1300
Concorde Supersonic Aeroplane, UK, France	1100	Troy and Greenfield Railroad, USA	900
		Canadian Firearms registry, Canada,	590



# Failure History

- 65% of project failures were due to softer aspects such as people, organization, governance.
- A further 21% were caused by management process and contracting and governance.
- 14% of the failure due to external factors such as government intervention and environment – related mandates



# Three guiding questions

- **Are cost overruns and construction delays inevitable features of Nuclear New Build (NNB) ? ?**
- **Is there single model for Project management or Business model in NNB ?**
- **What are the conditions for more efficient global nuclear supply chain for NNB ?**

# Focused on nuclear new build

## What's Demanded

**Planned Construction Time**

**Higher Quality**

**Within Budget**

**Localization and National Involvement**

## Need to Achieve

**Front-loaded Detailed Construction Engineering**

**Perfect Construction Management**

**Data Sharing & Technical Transfer Environment**

# Construction Period

Categories	1970-1995 [month]	1996-Now [month]
Median	80	83 ~ more than 200
Minimum	41	47


- Construction Schedule for 1350 MWe unit
  - From F/C to C/O : 62 → 49 Months
- Construction Schedule at 1000 MWe unit
  - From F/C to C/O : 64 → 47 Months

C/O: Commercial Operation

F/C : First concrete pouring

# Owner Establishment

## Owner Requirements for Success





---

# 02

## PART Two

### Previous Construction Experiences

---

# After first Criticality (Atuch #2) in Argentina

Net Capacity  
(PHWR KW)

692 Mw<sub>e</sub>

Construction

14 Jul, 198

First Grid C

27 Jun, 201




# Site Situation at the time of restarting the Project (2006) in Argentina



Preservation Program during suspension period  
40000 ton - 85000 Items - 95 Warehouses

# Angra 3 Npp in Brazil



- Began in 1984 but was suspended after two years.
- First concrete was poured in 2010. But stopped in 2015
- In 2022, Eletronuclear ordered construction to restart
- In April 2023 the city government ordered work to stop

# Angra 3 Npp in Brazil

## Preservation of Stored Components



In 2003 Photos

# Bushehr 1 NPP

Unit Power VVER-446	Design Net Capacity	Gross Capacity	Thermal Capacity
<b>915 MW<sub>e</sub></b>	<b>915 MW<sub>e</sub></b>	<b>1000 MW<sub>e</sub></b>	<b>3000 MW<sub>t</sub></b>
Construction Start Date	First Criticality Date	Construction Suspension Date	Construction Restart Date
<b>01 May, 1975</b>	<b>08 May, 2011</b>	<b>01 Jan, 1978</b>	<b>01 Jan, 1996</b>
First Grid Connection	Commercial Operation Date		17y 8m after resuming Construction
<b>03 Sep, 2011</b>	<b>23 Sep, 2013</b>		

## OL3 construction site in February 2012



0 MW<sub>th</sub>  
7 MW<sub>el</sub>  
%

*May 2008 : Start Hot Functional Tests*  
*Aug. 2008 : First Fuel Loading*  
*Nov. 2008 : First Criticality*  
*April 2009 : Start Demo-Run*

December 2012, Areva estimated full cost would be about €8.5 billion, well over previous estimate of €6.4 billion , with commercial operation no earlier than 2018.

Cost overruns were considerable, rising from the original estimate of €3.9 billion, to a final cost of €11 billion, split between TVO and Areva.



*April 2009 : Start Demo-Run*



**First 2022 : Start Demo-Run**



# EPR construction status



## EPR Taishan 1&2 (China)

- 2 × 1750 MW
- Construction began: 2009
- **Planned to go online in 2013**
- Commission date: June 2018
- Construction cost: 50.2 billion yuan (US\$7.5 billion)

**Taishan -1**



**Regulators in charge of EPR licensing :** NNSA+ASN+STUK+ONR  
**EPR owners :** TNPJVC+EDF+TVO+NNB  
**EPR designer :** AREVA

**5 years  
delayed**


**Taishan -2**

1 year after Taishan-1


# Westinghouse AP1000

## A compact station


- 3415 MWt.
- 1117 MWe
- 2-loops, 2 SGs



# Reduced Components




# Construction Duration – 56 Months (China construction- Sammen/ Haiyang)



# AP-1000, SANMAN CHINA




- Nov. 2013 Commercial Operation Date in Contract
- Aug.14 2018 COD



Westinghouse –EPC Contract

# Challenges - Design Management



## AP-1000, 4 units in USA

- **Construction began on the first of four AP1000 reactors in the USA**
  - **Summer unit 2 and Vogtle unit 3 in Georgia – March 2013,**
  - **Summer 3 unit and Vogtle 4 unit - November 2013**
- **Fixed prices**
- **Construction – 56 Months**

# USA V.C Summer unit 2, 3 AP 1000

24



Summer unit 2, pictured on 9 June after placement of the unit's third and final containment ring (image: SCE&G)

March 2013- Unit 2  
Nov. 2013 – Unit 3  
Start Construction

The end of July, 2017,  
Spent 9 B USD

**Westinghouse – EPC Contract**



# USA V.C Summer unit 2, 3 AP 1000



The unfinished Unit 2 nuclear reactor pictured Sept. 12, 2024, at VC Summer NPP construction site

# Nuclear reactor assemblies pictured Sept. 12, 2024



Reactor vessel pictured Sept. 12, 2024

# Vogtle unit 3 and 4 in Georgia

27



## Vogtle unit 3 in Georgia – approval of Fuel Loading : Aug. 04. 2022

Milestone	Unit 3	Unit 4
First Nuclear Concrete	March 2013	November 2013
First Sync to Grid	April 2023	October 2023 (F)

Cost of \$35 billion — More than double the initial \$14 billion estimate, seven years late

Ref : <https://scdailygazette.com/2024/10/15/7-years-after-sc-nuclear-debacle-advisory-group-suggests-potential-restart-of-failed-project/>

# Temelin NPP construction in Czech Republic



<b>PWR (VVER-320)</b>	<b>(3210 MWt/ 1023 Mwe)</b>
<b>Construction Start Date</b>	<b>First Criticality Date</b>
<b>01 Feb, 1987</b>	<b>11 Oct, 2000</b>
<b>First Grid Connection</b>	<b>Commercial Operation Date</b>
<b>21 Dec, 2000</b>	<b>10 Jun, 2002</b>




# Temelin commissioning challenges

**U1 individual Power Ascension Test = 525 days/ 1.43 year**

Power level	From – To	Days	Interruption	Note
<b>5%</b>	30 Oct – 10 Nov 2000	<b>12</b>	-	-
<b>12%</b>	14 Nov – 9 Dec 2000	<b>26</b>	-	-
<b>30%</b>	15 Dec 2000 – 8 Mar 2001	<b>84</b>	approx. 70 days	The stage was repeatedly interrupted with T/G
<b>55%</b>	19 Mar – 27 Sep 2001	<b>193</b>	3 Apr – 16 Apr [14 days] and 26 Apr – 12 Aug [109 days]	Vibration of the turbine and the pipeline between control valves and HP cylinder of T/G
<b>75%</b>	19 Oct - 18 Dec 2001	<b>61</b>	1 Nov – 26 Nov [26 days]	RCP autonomous circuit leak
<b>90%</b>	21 Dec 2001 – 3 Jan 2002	<b>14</b>	-	-
<b>100%</b>	10 Jan – 24 May 2002	<b>135</b>	24 Feb – 22 Apr [58 days]	Non-functionality of fast acting valves Argus

**The period between termination of the previous stage and the initiation of the subsequent stage is the period of waiting for the approval of State office for nuclear safety. = 1.7 years**

# 2009, 1<sup>st</sup> Export of APR1400 to UAE



Before site preparation in 2009



4 units construction completion in 2024



# Barakah Unit 1, 2, 3, 4 (UAE)

- **Design** : APR1400 x 4 units
- **Expected Cost**: 541 billion CZK
- **Construction Duration**
  - Unit 1: 2012 – 2021 (8.7 yrs)
  - Unit 2: 2013 – 2022 (8.5 yrs)
  - Unit 3: 2014 – 2023 (8.4 yrs)
  - Unit 4: 2015 – target to 2024
- **Project Schedule**



Major Milestone	Unit 1	Unit 2	Unit 3	Unit 4
Contract signed	2009			
Site Excavation	2011 – 2015			
1 <sup>st</sup> Concrete (after Construction License)	2012	2013	2014	2015
Reactor Installation	2014	2015	2016	2017
Fuel Loading (after Operation License)	2020	2021	2022	(2023)
Project Completion	2021	2022	2023	(2024)

## Senior Reactor Operator

- Reactor Power Plant Theory
- Plant Systems Training
- Formal Simulator Training
- Structured Reviews
- Simulator Exercises
- Final Examination

---




# 03

## PART Three


### Advanced Technology

---





# Advanced Water Cooled Reactor Technologies



# Construction Methods

---

Open Top Installation

---

Modularization

---

Advanced Welding Techniques

---

Steel Plate Reinforced Concrete Structures

---

All Weather Construction & Round the Clock Work

- **Concrete Composition Technologies**
- **Excavation Techniques**
- **Cable Installation**
- **Area Completion Schedule Management**
- **Application of Computer Systems for Information Management and Control**

# Open-top Construction HRP-1000, Zhangzhou Steam Generator installation



All three SGs for unit 2 of the Zhangzhou NNB in China's Fujian province have been installed over a five-day period,


The hoisting of the second **SGs took just 2 hours and 54 minutes**, "setting a new record in the history of nuclear power".

## Zhangzhou NPP Reactor Pressure Vessel Installation, Nov. 2. 2021




# Module categories : Structural module

CA01 25mX29mX26m, 750T




CA20 21mX14mX21m, 872T



# Modularization Design and Construction

- Parallel construction, shorten the construction period, Achieve manufactory
- pre-fabrication and pre-assembly, to improve the production quality


Nuclear Island	Struc. Module	Equip. Module	Total
Reactor Building	65	12	77
Auxiliary Building	19	42	61
Total	84(29)	54(59)	138(88turbine)



CA01-Struc. Module



Q601-Equip. Module



CA20-Struc. Module

# Modular Construction

Pros and Cons need to be evaluated based on the job site conditions


## Pro

- Reduce Schedule (If Module is applied to CP)
- Reduce Field Work and Levelled On-site Manpower
- Increase Productivity and Quality under Factory Environment
- More Safely and efficiently at Ground Level Work
- Reusability of PPM Engineering to the Nth Plants


## Con

- ✘ Increase Engineering for Module
- ✘ Increase Temporary Support Structure
- ✘ Early Material Requirements
- ✘ Additional Transportation Cost (Large trailer truck, Barge)
- ✘ Increase Lifting/Rigging Requirements (Crane, Lifting Jig)
- ✘ Inspection of Modular

# Construction Schedule with 6D




3D-model linked with Schedule






# Information system for engineering data management, based on 3D models





**NPP Component**



**Tabula Data**  
(weights, dimensions, dose rates etc.)

Наименование и техническая характеристика	Тип (марка)	Площадь поверхности ед-цы	Масса ед-цы	Количество шт.	Площадь поверхности	Общая масса
Аварийный маслоснаос уплотнений вала генератора Q=38 м3/час, N=26.4 кВт	ЦНСА 38-176	8.15 м2	630 кг	1 шт.	8,1 м2	630,0 кг
Аварийный питательный насос Q=65	ПЗА 65-56	14.21 м2	3540 кг	1 шт.	14,2 м2	3540,0 кг
подпиточный насос Q=48	ЭП-50	28.93 м2	5010 кг	2 шт.	57,9 м2	30020,0 кг
F=200 м2, V=4.3 м3	ПСС-200-7-15	72.36 м2	6810 кг	1 шт.	72,4 м2	6810,0 кг
F=125 м2, V=2.26 м3	ПСС-125-7-15	57.82 м2	4240 кг	1 шт.	57,8 м2	4240,0 кг
бак	ББВ-2	9.93 м2	430 кг	1 шт.	9,9 м2	430,0 кг
р		1.12 м2	30.55 кг	1 шт.	1,1 м2	30,5 кг
р	ФВ-25	1.44 м2	39.3 кг	2 шт.	2,9 м2	78,6 кг
р	ФС-400-1	10.32 м2	19.5 кг	3 шт.	31,0 м2	58,5 кг
р	ВГТ-2700-500	62.98 м2	4411.95 кг	1 шт.	63,0 м2	4412,0 кг
р	ВТ-50-3000	8.3 м2	2067.7 кг	1 шт.	8,3 м2	2067,7 кг
р	ТБ-6-2	105.95 м2	64300 кг	1 шт.	105,9 м2	64300,0 кг
р	ТВВ-200-2	371.35 м2	225380 кг	1 шт.	371,4 м2	225380,0 кг
р	бак V= 56 м3	118.98 м2		1 шт.	119,0 м2	-
р	20 м3	483.34 м2	36590 кг	1 шт.	483,3 м2	36590,0 кг
р	турбина	431.8 м2	260775 кг	1 шт.	431,8 м2	260775,0 кг



---

# 04

## Work force planning

---

### PART Five


# CENEN – CzEch Nuclear Education Network



## CENEN - CzEch Nuclear Education Network



- Czech nuclear education network
- 7 universities
- Free association without legal personality
- Partners from industry, research, etc state institutions
- Currently, there is an effort to revive the activities of the association and give it legal personality



## Goal

1. Analysis and prediction of human resources needs in the context of the current and planned nuclear activities of the Czech Republic.
2. Monitoring and cataloging of educational activities in the field of technical education
3. Support of technical education in the Czech Republic.
4. Preparation and implementation of educational events
5. Provision of advice and support, expert activities.
6. Implementation of educational activities.

# UZBEKISTAN PLANS TO BUILD NPP WITH 2 UNITS OF RUSSIAN VVER-1200 POWER REACTOR THE CAPACITY OF WHICH ARE 1,2 GW EACH (2,4 GW total capacity)



# NUMBER OF PERSONNEL IN THE NPP (PLANNED)


Subdivision	Number of persons
Management	235
Operation	537
Safety and reliability	234
Repairs/ Maintenance	211
Engineering support	24
Advanced Control System TP service and IT	475
Educational and training	48
Production and technical support and quality	42
Chief Inspector Division	24
Design support for the construction	17
Planning of supply and acquisition of equipment	9
Planning, economic and estimates	11
<b>TOTAL</b>	<b>1867</b>

# NUMBER OF TRAINED PERSONNEL WITH HIGHER EDUCATION

Years of graduate	2020	2021	2022	2023	2024	2025	2026	2027	2028	Total by 2028	2029	2030	Total by 2030
<b>Masters's degree</b>													
<b>Moscow Engineering Physics Institute</b>	15	30	30	30	30	30	30	30	30	<b>255</b>	30	30	<b>315</b>
<b>National University of Uzbekistan</b>		15	20	20	20	20	20	20	20	<b>155</b>	20	20	<b>195</b>
<b>Samarkand State University</b>		12	12	12	12	12	12	12	12	<b>96</b>	12	12	<b>120</b>
<b>TOTAL for master's degree</b>	<b>15</b>	<b>57</b>	<b>62</b>	<b>62</b>	<b>62</b>	<b>62</b>	<b>62</b>	<b>62</b>	<b>62</b>	<b>506</b>	<b>62</b>	<b>62</b>	<b>630</b>
<b>Bachelor's degree</b>													
<b>Tashkent branch of MEPHI</b>				100	100	100	100	100	100	<b>600</b>	100	100	<b>800</b>
<b>Tashkent State Technical University</b>			40	40	40	40	40	40	40	<b>280</b>	40	40	<b>800</b>
<b>TOTAL for bachelor's degree</b>			<b>40</b>	<b>140</b>	<b>140</b>	<b>140</b>	<b>140</b>	<b>140</b>	<b>140</b>	<b>880</b>	<b>140</b>	<b>140</b>	<b>1160</b>
<b>TOTAL</b>	<b>15</b>	<b>57</b>	<b>102</b>	<b>202</b>	<b>202</b>	<b>202</b>	<b>202</b>	<b>202</b>	<b>202</b>	<b>1 386</b>	<b>202</b>	<b>202</b>	<b>1 790</b>

As a result of the implementation of the personnel training programme, the required number of personnel with higher education (*1567 people*) will be prepared for the needs of the NPP with a reserve of **223** people.

# Typical Site Skills Profile – Twin Unit Site







# Future New Nuclear Build in Europe

## Success of NNB will depend on

- Securing Supply Chains,
- Addressing Labor Shortages,
- Ensuring Regulatory Efficiency,
- Making the Financial Cases

All of them will begin at the end of 2020 and become operational by mid-2030.





# Recommendations

- **Establish a Long-Term Plan for Human Resource Development**
  - How can we support the development of 6 to 9 GWe of new nuclear capacity?
  - After the handover from the EPC (Engineering, Procurement, and Construction) contractor, who will be responsible for operating the newly built nuclear power plants (NPPs)?
    - For the operation of an NPP, we require 6 shifts.
    - Each team should consist of 10 operators: 5 operators in the Main Control Room (including SRO, RO, TO, EO, SA) and 5 operators in the Local Control Room.
- **Consider setting up a Polish Nuclear Education Network similar to CENEN**
  - Develop a joint research policy project focused on human resource development (HRD).

CENEN : Czech Nuclear Education Network